



# Tee-Panel Roll Former

## BERRIDGE SS-14



*The Berridge Model SS-14 Portable Roll-Former forms continuous-length, eave-to-ridge straight Berridge Tee-Panels, and Curved Tee-Panels. The Berridge Model SS-14 Portable Roll Former also curves the factory-formed seam caps.*



### MATERIAL

24 GA Galvalume®

Limited Availability: 22 GA Galvalume® and 0.032 Aluminum

### COIL & COVERAGE

**Coil Size:** Nominal 14" (13 7/8")

**Coil Quantity:** Requires 109.80 SF of coil per square of coverage

**Snap-on Seams:** Requires 94.12 LF of seams per square of coverage (Factory Formed)

### MINIMUM CURVING RADII


Convex: 4'

Concave: 6' (Consult BMC for smaller radii)

### ACCESSORIES

**Tee-Clips:** 80 clips per square (use typically at 20" o.c.); Use 24 GA clip with Galvalume® Panels or Stainless clip with Aluminum or Copper Panels

**Folding Tee-Clips:** 80 clips per square (use typically at 20" o.c.); Use with curved panels, 28 Gauge material



### SPECIFICATIONS

Mounted on heavy duty 4-wheel table

**Width:** 35" **Length:** 88" **Height:** 53"

**Weight:** 1,470 lbs with shipping cover

- 2 HP electric motor - 110V single-phase current
- High Speed - 45' per minute
- Built-in uncoiler (up to 2,000 lb coil)
- Stainless steel heat-treated, hardened rollers
- Unique side production for ease of operation
- Mechanical slitter shear
- Accurate-length gauge (computer optional)
- Forms continuous-length panels
- All sealed bearings
- Coil handling apparatus included
- Curves panels and seams



*Pictured Above*

Project: Skyview at Fall River Village

General Contractor: Prime Homes, LLC, Architectural Panels, Inc.

Installing Contractor: CCG Roofing & Project Management

Color: Zinc Grey