ZEE-LOCK PANEL INSTALLATION DETAILS



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

800-669-0009 • www.Berridge.com

THE DETAILS CONTAINED IN THE FOLLOWING PAGES ARE MERELY RECOMMENDATIONS AS TO HOW BERRIDGE MANUFACTURING MATERIALS SHOULD BE INSTALLED. THEY MAY REQUIRE ADAPTATIONS OR MODIFICATIONS FOR A SPECIFIC PROJECT AS CONDITIONS VARY IN BOTH BUILDING DESIGN AND LOCAL WETHER PECULIARITIES.

BERRIDGE MANUFACTURING COMPANY SHOULD BE HELD HARMLESS FROM ANY AND ALL CLAIMS ARISING FROM LACK OF WATERTIGHTNESS AS A RESULT OF FOLLOWING THESE RECOMMENDED DETAILS. ENSURING WATERTIGHTNESS ON ANY GIVEN PROJECT IS THE FUNCTION OF THE INSTALLER. THE ARCHITECT/GENERAL CONTRACTOR/INSTALLER MUST ACCEPT THE RESPONSIBILITY TO ADAPT
THESE DETAILS TO MEET PARTICULAR BUILDING REQUIREMENTS AND TO ASSURE ADEQUATE WATERTIGHTNESS.

THE INSTALLER CAN VIRTUALLY ASSURE WATERTIGHTNESS IF THESE FLASHINGS DETAILS HAVE BEEN PROPERLY ADAPTED, ADEQUATE LAPS HAVE BEEN PROVIDED, CORRECT TYPE OF SEALANT USED, ALL JOINTS ADEQUATELY CAULKED, AND PROFESSIONAL WORKMANSHIP EMPLOYED.

A. BERRIDGE ZEE–LOCK PANEL: THE ZEE–LOCK PANEL IS FACTORY FABRICATED AND/OR FIELD FABRICATED (USING THE BERRIDGE SP–21 PORTABLE ROLL FORMER) TO A CONSTANT PAN WIDTH OF 16" AND A CONSTANT SEAM HEIGHT OF 2".

THE BERRIDGE ZEE–LOCK SIDE LAPS ARE MECHANICALLY SEAMED IN THE FIELD WITH THE BERRIDGE POWER DRIVEN SEAMER MACHINE.

B. MINIMUM SLOPE: THE ZEE–LOCK PANEL IS RECOMMENDED FOR ROOF SLOPES OF 1:12 AND GREATER. CONSULT BERRIDGE'S TECHNICAL DEPARTMENT FOR ANY SLOPE REQUIREMENTS LESS THAN 1:12.

A DOUBLE LAYER #30 FELT UNDERLAYMENT OR 1 LAYER OF BERRIDGE APPROVED PEEL AND STICK UNDERLAYMENT COVERING THE ENTIRE SUBSTRATE IS RECOMMENDED FOR ALL APPLICATIONS WHERE THE ROOF SLOPE IS 3:12 OR LESS.

C. MATERIAL STORAGE: CAUTION MUST BE EXERCISED IN STORAGE OF MATERIAL PRIOR TO INSTALLATION. KEEP ALL BERRIDGE PREFINISHED MATERIAL IN A DRY LOCATION WITH ADEQUATE VENTILATION AND OUT OF DIRECT SUNLIGHT.

EXPOSURE TO DIRECT SUNLIGHT AND/OR MOISTURE MAY CAUSE THE FACTORY APPLIED STRIPPABLE PLASTIC FILM TO ADHERE TO THE METAL PERMANENTLY AND DISCOLOR THE FINISH. IF THIS SHOULD OCCUR THE PAINT WARRANTY WILL BE VOID.

D. STRIPPABLE FILM: THE STRIPPABLE PLASTIC FILM WHICH IS APPLIED OVER MOST BERRIDGE PREFINISHED PRODUCTS, PANELS, FLASHINGS, COILS AND FLAT SHEETS MUST BE REMOVED PRIOR TO INSTALLATION

E. SOLID SHEATHING REQUIREMENTS: BERRIDGE MANUFACTURING COMPANY RECOMMENDS THE USE OF EITHER A MINIMUM 22 GAUGE CORRUGATED METAL DECK OR A MINIMUM OF 1/2" WOOD SHEATHING TO PROVIDE SUFFICIENT HOLDING POWER FOR FASTENERS. CONTACT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT FOR USE OF ANY OTHER TYPE OF SOLID SHEATHING. SUBSTRATE SHOULD BE LEVEL TO 1/4" IN 20'–0".

FOR ASSEMBLIES WITH RIGID INSULATION OVER THE STRUCTURAL DECK, PROVIDE WOOD BLOCKING EQUAL TO THE DEPTH OF THE INSULATION AT THE PERIMETERS.

DUE TO THE TENDENCY OF #30 FELT TO TEAR WHEN USED DIRECTLY OVER A CORRUGATED DECK, BERRIDGE RECOMMENDS THAT THE ARCHITECT, DESIGNER, AND/OR INSTALLER REVIEW THE USE OF A BERRIDGE APPROVED PEEL AND STICK UNDERLAYMENT AND FOLLOW PRODUCT INSTALLATION INSTRUCTIONS FROM SAID UNDERLAYMENT MANUFACTURER PRIOR TO INCORPORATION INTO ANY PROJECT.

NOTE: FOR PROJECTS REQUIRING UL 90 ASSEMBLY, REFER TO UL 90 DETAILS.

F. SHEATHING INSPECTION:

1. SHEATHING END JOINTS SHOULD BE STAGGERED.

2. ALL END JOINTS SHOULD MEET AT EITHER A JOIST OR RAFTER.

3. BLOCKING OR "H" CLIPS SHOULD BE USED IF JOINTS DO NOT REMAIN FLAT UNDER THE WEIGHT OF WORKMEN.

4. USE SHIMS TO KEEP ENTIRE SUBSTRATE EVEN; UNEVEN SUBSTRATE WILL RESULT IN "OIL–CANNING" IN THE PANELS. SUBSTRATE SHOULD BE LEVEL TO 1/4" IN 20'–0".

5. ALL CUTS AT PENETRATIONS SHOULD BE TIGHT, WITHOUT GAPS.

6. USE WOOD FRAMED CRICKETS AT LARGE PENETRATIONS.

7. MAKE SURE SUBSTRATE JOINTS ARE TIGHT AT ALL HIPS, VALLEYS AND RIDGES.

G. INSTALLATION OVER OPEN FRAMING: DIAPHRAGM CAPABILITIES AND PURLIN STABILITY ARE NEGLIGIBLE AS PROVIDED BY THE BERRIDGE ZEE–LOCK PANEL SYSTEM, THEREFORE OTHER BRACING WILL BE REQUIRED TO CONFORM TO AISI SPECIFICATIONS.

H. OPEN FRAMING INSPECTION:

1. PURLINS SHOULD BE ALIGNED WITH TOP FLANGES IN THE SAME PLANE TO A TOLERANCE OF 1/4" IN 20'–0". UNEVENNESS IN THE TOP PLANE OF THE PURLINS WILL RESULT IN ABNORMAL "OIL CANNING" PANELS. PURLINS SHALL BE ADEQUATELY BRACED.

2. BERRIDGE MANUFACTURING COMPANY RECOMMENDS SOLID SHEATHING IN VALLEY AND AROUND ROOF PENETRATIONS. DO NOT APPLY PANELS ON OPEN FRAMING AT VALLEYS OR ROOF PENETRATIONS WITHOUT REFERING TO DETAILS Z–72, Z–72T, Z–85 AND Z–86.

3. FOOT TRAFFIC ON THE PANELS MUST BE KEPT TO A MINIMUM. ARCHITECTURAL PANELS ARE DESIGNED FOR AESTHETICS AND CAN BE EASILY DAMAGED OR DEFORMED IF EXTREME CARE IS NOT USED.

I. FASCIA/RAKE INSPECTION:

1. STRIKE A LINE THE FULL LENGTH OF THE FASCIA OR RAKE. IF NOT STRAIGHT, CORRECT WITH SHIMS.

2. MAKE SURE FASCIA/RAKE IS FLUSH WITH SHEATHING.

J. UNDERLAYMENT: MINIMUM #30 FELT OR BERRIDGE APPROVED 40 MIL MINIMUM, HIGH TEMPERATURE PEEL & STICK UNDERLAYMENT MUST BE APPLIED OVER SOLID SHEATHING AS SHOWN IN THE BERRIDGE MANUFACTURING COMPANY TYPICAL ZEE–LOCK, AND UNDERLAYMENT INSTALLATION DETAILS. THE USE OF ADDITIONAL LAYERS OF UNDERLAYMENT IS REQUIRED ON LOW–SLOPED ROOFS, AT ALL VALLEY CONDITIONS, AT ROOF PENETRATIONS, AND CERTAIN OTHER FLASHING CONDITIONS AS DEPICTED THROUGHOUT THE ZEE–LOCK TYPICAL DETAILS. BERRIDGE REQUIRES STRIP IN LAYERS OF #30 FELT UNDERLAYMENT TO BE MINIMUM 36" OR A FULL ROLL AT ALL FLASHING LOCATIONS; FOR BERRIDGE APPROVED PEEL & STICK A 36" OR FULL ROLL AT VALLEY FLASHING AND SQUARE ROOF PENETRATION LOCATIONS, AND MINIMUM 12" AT ALL OTHER FLASHING LOCATIONS. BERRIDGE APPROVED PEEL AND STICK UNDERLAYMENT MAY BE REQUIRED ON LOW SLOPED ROOFS OR AT CERTAIN FLASHING CONDITIONS. FOR ALL WATERTIGHTNESS WARRANTIES, THE UNDERLAYMENT MUST BE THE BERRIDGE APPROVED PEEL AND STICK UNDERLAYMENT. BOTH UNDERLAYMENT INSTALLATION DETAILS AND APPROVED UNDERLAYMENTS AND SEALANTS LIST CAN BE FOUND ON BERRIDGE'S WEBSITE: WWW.BERRIDGE.COM

APPROVED UNDERLAYMENTS AND SEALANTS

UNDERLAYMENT INSTALLATION DETAILS

K. UNDERLAYMENT INSTALLATION:

1. DO NOT USE ROSIN PAPER UNDER METAL ROOFING PANELS.
2. SWEEP ROOF AREA CLEAN.
3. WHEN UTILIZING FELT, USE FLAT HEAD GALVANIZED ROOFING NAILS X 1–1/4" LONG OR A #12 PANCAKE HEAD COATED FASTENER WITH BERRIDGE GALVANIZED FELT CAPS.
4. INSTALL VALLEY UNDERLAYMENT FIRST.
5. INSTALL UNDERLAYMENT PARALLEL TO EAVE (2 LAYERS REQUIRED AT EAVE), STARTING AT EAVE AND USING MINIMUM 6" LAPS. 2 LAYERS REQUIRED AT EAVE REGARDLESS OF SLOPE.
6. REFER TO UNDERLAYMENT DETAILS WHEN VALLEYS OR ROOF PENETRATIONS ARE INVOLVED.
7. INSULATE BETWEEN WOOD BLOCKING AND METAL WITH #30 FELT OR BERRIDGE APPROVED PEEL AND STICK UNDERLAYMENT.

L. THERMAL MOVEMENT: EXPANSION AND CONTRACTION OF METAL PANELS WHICH EXCEED THIRTY FEET IN LENGTH CAN BE A FACTOR IN THE DESIGN AND INSTALLATION OF FLASHING. PLEASE REFER TO THE GALVALUME LINEAR EXPANSION CHART ON PAGE ZI–6 (GL) TO DETERMINE ANTICIPATED THERMAL MOVEMENT OF THE PANELS. IMPROPERLY DESIGNED FLASHING CAN ALLOW PANELS TO DISENGAGE FROM THE FLASHING, ALLOW OIL–CANNING IN THE PANEL AND/OR CAUSE FLASHING TO WORK LOOSE FORM ITS ANCHORAGE.

PANELS OVER 30'–0" LONG REQUIRE EXPANSION CLIPS WHEN USED WITH CONTINUOUS ZEE–RIB. REFER TO DETAIL Z–5 OVER SOLID SHEATHING, AN ALTERNATE DETAIL Z–6 MAY BE UTILIZED WITH ZEE–RIBS OF 10'–0" OR LESS.

M. ELECTROLYSIS: AVOID ALLOWING FLASHINGS AND PANELS TO COME INTO CONTACT WITH EITHER LEAD OR COPPER AND PREVENT EXPOSURE TO WATER RUNDOWN FROM COPPER AND/OR LEAD.

N. SEALANT REQUIREMENTS: FOR A FULL LIST OF APPROVED SEALANTS VISIT: WWW.BERRIDGE.COM
APPROVED UNDERLAYMENTS AND SEALANTS

O. FLASHING: IF BERRIDGE MANUFACTURING COMPANY IS TO SUPPLY FLASHINGS, ALL FLASHINGS WILL BE FABRICATED IN 10'–0" LENGTHS WITH SQUARE END CUTS ONLY. THE PURCHASER MUST PROVIDE ALL DIMENSIONS AND DEGREE OF ANGLES.

FLASHING INSTALLATION:

1. REMOVE STRIPPABLE PLASTIC FILM FROM ALL FLASHINGS PRIOR TO INSTALLATION.
2. ALWAYS STAGGER JOINTS WHEN ONE FLASHING IS INSTALLED OVER OTHER FLASHINGS.
3. INSTALL ALL FLASHINGS AS PER BERRIDGE TYPICAL DETAILS.
4. ALL FLASHINGS ARE TO BE DESIGNED AND INSTALLED TO NOT TRAP WATER.

NOTE: WHEN USING POP RIVETS ON FLASHING, STAINLESS STEEL RIVETS ARE RECOMMENDED TO AVOID RUST STAINS. USE #12 PANCAKE HEAD ZINC PLATED FASTENERS FOR FLASHING INSTALLATION. MAKE SURE ALL FASTENERS ARE DRIVEN STRAIGHT AND SET FLAT. DO NOT OVERDRIVE FASTENERS AS THIS WILL CAUSE THE FLASHINGS TO BUCKLE OR BECOME RECESSED BELOW THE ELEVATION OF THE SUBSTRATE.

P. PANELS: BERRIDGE MANUFACTURING COMPANY WILL PROVIDE SQUARE END CUTS ONLY ON ALL ZEE–LOCK PANELS. COMPUTATION OF ALL QUANTITIES AND DIMENSIONS ARE THE RESPONSIBILITY OF THE PURCHASER. PANELS ARE TO BE FIELD CUT WITH SNIPS, NIBBLER, AND/OR SHEARS ONLY.

Q. PANEL INSTALLATION:

1. REMOVE STRIPPABLE PLASTIC FILM FROM EACH PANEL PRIOR TO INSTALLATION.

2. START PANEL INSTALLATION AT GABLE END OF THE ROOF, WORKING TOWARD THE OTHER GABLE END. MAKE SURE PANELS ARE PERPENDICULAR TO THE EAVE. AT VALLEY AREAS, MAKE SURE PANELS ARE INSTALLED SO THAT DRAINAGE HAS FREE FLOW AND IS NOT OBSTRUCTED BY PANEL SEAMS.

3. INSTALL THE CONTINUOUS ZEE–RIB OR ZEE–LOCK CLIPS ALONG THE LEADING MALE LEG OF EACH PANEL AS PER BERRIDGE TYPICAL DETAILS AND INSTALLATION NOTES.

4. USE BERRIDGE SEAMER AT PANEL SIDE LAPS.

5. EACH PANEL IS TO BE KEPT TIGHT AGAINST THE LEG OF THE ADJOINING PANEL. NEVER PERMIT A GAP BETWEEN VERTICAL LEGS. ANY CRIMPS IN VERTICAL LEGS MUST BE STRAIGHTENED (TOTALLY STRAIGHT WITHOUT ANY BENDS, CRIMPS, CREASES, ETC.) PRIOR TO SEAM INSTALLATION.

6. KEEP PANELS ALIGNED SO THAT SEAMS MATCH AT HIPS, VALLEYS AND WHERE VERTICAL PANELS ADJOIN ROOF PANELS. DO NOT INSTALL LONG CONTINUOUS RUNS OF PANELS ALL AT ONE TIME WHERE SEAM LINES MUST MATCH. INSTALL TEN OR TWELVE PANELS IN ONE ELEVATION AND THEN FOLLOW WITH A LIKE NUMBER OF PANELS ON THE OTHER ELEVATION. WHEN YOU INSTALL PANELS IN THIS MANNER, YOU WILL BE ABLE TO MAKE ANY ADJUSTMENTS REQUIRED TO INSURE SEAM MATCHING.

7. METALLIC FINISHES:
PANEL INSTALLATION: NOTE THE SERIES OF ARROWS PAINTED ON THE UNDERSIDE OF THE PANEL. ALL PANELS MUST BE INSTALLED IN CONSISTENT MANNER, MEANING THAT THE ARROWS ON EVERY PANEL ARE ALL POINTING IN THE SAME DIRECTION. IF A PANEL IS REVERSED (ARROWS POINTING OPPOSITE OF THOSE ON OTHER PANELS) IT WILL APPEAR FROM A DISTANCE, A DIFFERENT SHADE DUE TO THE GRANULAR EFFECT OF THE PIGMENTS IN THE FINISH. METALLIC FINISHES ARE MATCH – LOT FINISHES. DO NOT MIX LOTS.

R. PANEL SEAM: THE BERRIDGE ZEE–LOCK PANEL IS A MECHANICALLY SEAMED PANEL BY USE OF A BERRIDGE SEAMER MACHINE.

S. SEAMER INSTRUCTIONS:

1. PREPARE THE SIDE LAP SEAM FOR MACHINE SEAMING BY CRIMPING THE STARTING END OF THE SIDE LAP USING THE BERRIDGE HAND CRIMPER TOOL. THIS CREATES A SEAMED AREA WHERE THE SEAMER MACHINE WILL BE POSITIONED TO COMMENCE SEAMING THE SIDE LAP.

2. HAND SEAM TERMINATING END OF SIDE LAP IF OBSTRUCTION PREVENTS SEAMING MACHINE FROM SEAMING SIDE LAP ALL THE WAY UP TO THE END.

3. DO NOT LET SEAMER TRAVEL OFF END OF PANEL AND OVER EDGE OF EAVE. SEAMER DOES NOT AUTOMATICALLY SHUT OFF AT END OF SEAM.

4. ROOF SLOPES WITH A RISE OF MORE THAN 6" ON 12" SHOULD BE SEAMED IN A DOWNHILL DIRECTION. ATTEMPTING TO RUN SEAMER UP HILL ON STEEP SLOPE ROOFS MAY CAUSE ROLLER DIES TO SLIP AND RUB PAINT OFF PANEL LEGS.

5. REFER TO OPERATIONS MANUAL FOR IN–DEPTH INSTRUCTIONS AND MAINTENANCE PROCEDURES.

6. THE MACHINE SEAMING OF THE ZEE–LOCK PANEL IS DONE IMMEDIATELY AFTER THE INSTALLATION OF EACH PANEL.

T1. CONTINUOUS ZEE–RIB:

1. INSTALL ZEE–RIB AS PER BERRIDGE TYPICAL ZEE–LOCK PANEL DETAILS.

2. THE ZEE–RIB IS TO RUN CONTINUOUS ALONG THE ENTIRE LENGTH OF THE PANELS. IF PANEL LENGTH IS OVER 30'–0" LONG OR EXPANSION AND CONTRACTION OF PANELS IS A DESIGN FACTOR, REFER TO DETAIL Z–5. ALTERNATE DETAIL Z–6 MAY BE UTILIZED WITH ZEE–RIBS OF 10'–0" OR LESS.

3. VINYL WEATHERSEAL REQUIRED FOR INSTALLATIONS OVER OPEN FRAMING.

4. VINYL WEATHERSEAL REQUIRED FOR WARRANTIES.

T2. ZEE–LOCK CLIPS:

1. INSTALL FLOATING ZEE–LOCK CLIPS OR ZEE–LOCK CLIPS AS PER BERRIDGE TYPICAL ZEE–LOCK PANEL DETAILS.

*NOTE: IF LOCAL CODES OR OTHER REGULATIONS DICTATE SPECIFIC WIND UPLIFT REQUIREMENTS, CONSULT BERRIDGE ENGINEERING DEPARTMENT, AS IT MAY BE NECESSARY TO USE A DIFFERENT FASTENER PATTERN.

U. FASTENERS: INSTALL FASTENERS AS PER TYPICAL DETAILS. USE LOAD CHARTS UNDER THE "DOWNLOADS" TAB ON WWW.BERRIDGE.COM FOR FASTENER RECOMMENDATIONS ACCORDING TO SUBSTRATE.**

ZEE–LOCK LOAD CHARTS

MAKE SURE ALL FASTENERS ARE DRIVEN STRAIGHT AND SET FLAT. DO NOT OVERDRIVE FASTENERS AS THIS WILL CAUSE THE CLIP AND/OR FLASHINGS TO BUCKLE OR BECOME RECESSED BELOW THE ELEVATION OF THE SUBSTRATE.

**CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING THE USE OF ANY OTHER TYPE OF FASTENER.

V. UNDERWRITERS LABORATORIES RATINGS: THE BERRIDGE ZEE–LOCK PANEL COMPLIES WITH UL TEST PROCEDURE NO. 580 "TEST FOR WIND UPLIFT RESISTANCE OF ROOF ASSEMBLIES" CLASS UL 90 REFER TO DETAILS Z–90 – Z–96, REFER TO DETAILS Z–100 – Z–102 FOR HOURLY UL FIRE RESISTANCE DESIGN ASSEMBLIES.

BERRIDGE MANUFACTURING COMPANY STRIVES TO PROVIDE ITS CUSTOMERS WITH THE HIGHEST QUALITY STRETCHER LEVELED STEEL AVAILABLE. THE LATEST TECHNOLOGY IS ALSO INCORPORATED IN BERRIDGE'S HIGH–PRECISION COIL HANDLING AND ROLL FORMING EQUIPMENT TO MINIMIZE THE STRESS ON METAL DURING PRODUCTION. ALL THESE MEASURES HAVE BEEN TAKEN TO MINIMIZE THE AMOUNT OF "OIL–CANNING" (WAVINESS) WHICH IS NATURALLY INHERENT IN FLAT SHEET METAL. MANY TIMES; HOWEVER, THE CAUSE OF WAVINESS OR "OIL–CANNING" CAN BE TRACED TO UNEVEN SHEATHING, IMPROPER UNDERLAYMENT INSTALLATION, OR IN THE CASE OF OPEN FRAMING, UNEVENNESS OF THE TOP PLANE OF THE PURLINS OR FOOT TRAFFIC ON THE PANELS.

ALL ARCHITECTURAL PANELS REQUIRE CARE IN HANDLING AND INSTALLATION TO AVOID DAMAGING OR DEFORMING THE PANELS.

THESE INSTALLATION INSTRUCTIONS AND THE FOLLOWING TYPICAL DETAILS ARE INTENDED TO PROVIDE OUR CUSTOMERS WITH THE INFORMATION REQUIRED FOR AN AESTHETICALLY PLEASING AND FUNCTIONAL INSTALLATION OF THE BERRIDGE ZEE–LOCK PANEL SYSTEM.

NOTE: ALL PRODUCT SPECIFICATIONS, DETAILS AND INSTALLATION INSTRUCTIONS SUBJECT TO CHANGE WITHOUT NOTICE. FOR SPECIFIC PROJECT DETAILS, CONTACT BERRIDGE.





CONTINUOUS ZEE–RIB WITH (OPTIONAL) VINYL WEATHERSEAL



PANEL SECTION
24 OR 22 GAUGE STEEL



PANEL SUPPORT (OPTIONAL)



SEAM SECTION

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PANEL OVERVIEW
CONTINUOUS ZEE–RIB WITH VINYL WEATHERSEAL

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–4

NOT TO SCALE



1. FOR RIBS LESS THAN OR EQUAL TO 10'0" OVER SOLID SHEATHING, AN ALTERNATE DETAIL Z-6 MAY BE USED.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

EXPANSION JOINT DETAIL

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-5



EXPANSION AND CONTRACTION OF METAL PANELS DUE TO LONGITUDINAL THERMAL MOVEMENT MUST BE CONSIDERED IN BOTH DESIGN AND INSTALLATION. THE ABOVE CHART EMPHASIZES THE NEED TO PROVIDE AMPLE CLEARANCES FROM GUTTERS, RIDGES, ENDWALL, ETC.

MAXIMUM TEMPERATURE SHOULD BE NO LOWER THAN 140°F FOR WHITE PANELS, UP TO 180° FOR DARK PAINTED PANELS, REGARDLESS OF AMBIENT MAXIMUM, MINIMUM SHOULD BE FIGURED WELL BELOW AMBIENT MINIMUM TO ALLOW FOR RADIATION TO NIGHT SKY. IN ANY CASE, A MINIMUM OF 100°F DIFFERENTIAL IS RECOMMENDED.

NOT TO SCALE



1. ONLY FOR USE WITH 10'–0" ZEE RIB, SEE ALTERNATE DETAIL Z–5 FOR ZEE RIB LONGER THAN 10 FEET.
2. NOT FOR USE OVER OPEN FRAMING.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

BEARING PLATE DETAIL

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–6





CONTINUOUS ZEE–RIB



PANEL SECTION

NOTE: THIS PANEL DOES NOT
USE VINYL WEATHERSEAL



SEAM SECTION

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PANEL OVERVIEW
CONTINUOUS 3" ZEE–RIB

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–7



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

EAVE DETAIL; PANEL TURNDOWN OPEN FRAMING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–10



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. THE 3" ZEE–RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".

4. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING



EAVE SUPPORT FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

EAVE DETAIL; 3" ZEE–RIB OPEN FRAMING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–10GT



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE WITH GUTTER DETAIL OPEN FRAMING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–10PG



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE DETAIL; PANEL TURNDOWN SOLID SHEATHING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–11



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE DETAIL; PANEL TURNDOWN SOLID SHEATHING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–11F



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE WITH GUTTER DETAIL SOLID SHEATHING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–11FG



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE WITH GUTTER DETAIL SOLID SHEATHING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–11G



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

EAVE DETAIL; PANEL TURNDOWN SOLID SHEATHING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–11P



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE WITH GUTTER DETAIL SOLID SHEATHING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–11PG



1. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



MIN. 16 GA. SUB-FLASHING



RIDGE/HIP CAP

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RIDGE/HIP DETAIL OPEN FRAMING

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE
Z-20



1. THE 3" ZEE-RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



MIN. 16 GA. SUB-FLASHING



RIDGE/HIP CAP

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RIDGE/HIP DETAIL; 3" ZEE-RIB OPEN FRAMING

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE
Z-20T



NOTE: THERMAL BLOCK MATERIAL IS 25 PSI. DO NOT OVERDRIVE THE FASTENERS

F = FINISH SIDE



RIDGE CAP



CONTINUOUS CLEAT



ZEE CLOSURE



16 GA. SUB FLASHING



RIDGE FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

VENTED RIDGE DETAIL; 3" ZEE-RIB OPEN FRAMING

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE

Z-20TV



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, SUB-FLASHING WITH FASTENERS AT 20" O.C. MAX. IS REQUIRED.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RIDGE/HIP CAP



ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RIDGE/HIP DETAIL SOLID SHEATHING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-21



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.
2. RIDGE VENT MATERIAL TO BE COR-A-VENT. FOR QUESTIONS CONTACT COR-A-VENT AT 800-837-8368
3. THIS DETAIL TO ONLY BE UTILIZED IN CONJUNCTION WITH A VENTED SOFFIT OR MEANS TO BALANCE THE AIR FLOW THROUGH THE SYSTEM.
4. WHILE A PROPERLY DESIGNED RIDGE VENT WITH WATER SHIELDING MATERIAL IS OF VITAL IMPORTANCE, OR EQUAL CONCERN IS THAT THE ARCHITECT DESIGN FOR PROPER AIR FLOW; OTHERWISE THE RIDGE VENT WILL NOT FUNCTION. POSITIVE, OUTWARD AIR FLOW FROM A RIDGE VENT IS BASED ON THE FACT THAT WARM AIR RISES AND THAT THERE IS ADEQUATE INCOMING AIR AT THE ATTIC LOW POINT.
5. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RIDGE CAP



CONTINUOUS CLEAT



RIDGE FLASHING



ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

VENTED RIDGE DETAIL SOLID SHEATHING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-21V



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



RIDGE CAP



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

SHED RIDGE DETAIL SOLID SHEATHING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-22



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



RIDGE CAP



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

SHED RIDGE DETAIL SOLID SHEATHING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-22F



1. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



RIDGE CAP



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

SHED RIDGE DETAIL OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-220P



1. THE 3" ZEE-RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RIDGE CAP



MIN. 16 GA. SUB-FLASHING



CONTINUOUS CLEAT



ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

SHED RIDGE DETAIL SOLID SHEATHING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-220T



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



RIDGE CAP



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

SHED RIDGE DETAIL SOLID SHEATHING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-22P



1. ZEE CLOSURE IS DIE FORMED TO FIT PERPENDICULARLY BETWEEN PANEL SEAMS.



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

ZEE–LOCK RIDGE CLOSURE

DATE: 5/23

PAGE\FILE

Z–23

ZEE–LOCK PANEL

SECTION VIEW



PLAN VIEW



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

RIDGE TERMINATION SLOPES LESS THAN 3:12

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE

Z–24

SECTION VIEW



PLAN VIEW



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

RIDGE TERMINATION SLOPES GREATER THAN 3:12

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE

Z–24A



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



DRIP FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL
PANEL TURNDOWN
SOLID SUBSTRATE

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–30



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



DRIP FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL WITH FASCIA FLASHING; PANEL TURNDOWN SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–30F



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



DRIP FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL W/ WALL PANEL PANEL TURNDOWN SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–30P



1. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



DRIP FLASHING



MIN. 16 GA. SUB–FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL PANEL TURNDOWN OPEN FRAMING

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–31



1. THE 3" ZEE–RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



DRIP FLASHING



MIN. 16 GA. SUB–FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL; 3" ZEE–RIB PANEL TURNDOWN OPEN FRAMING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–31T



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CLOSURE FLASHING



DRIP FLASHING



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL CLOSURE FLASHING SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-33C



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CLOSURE FLASHING



DRIP FLASHING



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

GABLE DETAIL WITH FASCIA FLASHING; CLOSURE FLASHING SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-33CF



1. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CLOSURE FLASHING



MIN. 16 GA. SUB-FLASHING



CONTINUOUS CLEAT



DRIP FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL CLOSURE FLASHING OPEN FRAMING

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE
Z-33C0



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CLOSURE FLASHING



DRIP FLASHING



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

GABLE DETAIL W/ WALL PANEL CLOSURE FLASHING SOLID SUBSTRATE

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE
Z-33CP



1. THE 3" ZEE-RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CLOSURE FLASHING



DRIP FLASHING



MIN. 16 GA. SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL; 3" ZEE-RIB CLOSURE FLASHING OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-33T



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. WHEN THIS DETAIL IS USED DIRECTLY OVER RIGID INSULATION, WOOD BLOCKING OR A MINIMUM 16 GA. SUPPORT IS REQUIRED FOR THE STRUCTURAL ATTACHMENT OF FASTENERS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



DRIP FLASHING



SPECIAL ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

GABLE DETAIL ZL WALL PANEL SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–35





BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

DUTCH GABLE DETAIL

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE

Z-38



1. THIS DETAIL INTENDED FOR USE ON PARAPETS LESS THAN 12" IN HEIGHT, USE HEAD WALL DETAILS FOR ANY LARGER.

2. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CONTINUOUS CLEAT



CAP FLASHING



ZEE CLOSURE



COUNTER FLASHING



SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PARAPET DETAIL HEAD WALL SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-40



1. THIS DETAIL INTENDED FOR USE ON PARAPETS LESS THAN 12" IN HEIGHT, USE RAKE WALL DETAILS FOR ANY LARGER.

2. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



CAP FLASHING



CONTINUOUS CLEAT

COUNTER FLASHING



SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PARAPET DETAIL RAKE WALL SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-41



1. THE 3" ZEE-RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



RECIEVER FLASHING



COUNTER FLASHING



COUNTER FLASHING



MIN. 16 GA. SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

HEAD WALL DETAIL; 3" ZEE-RIB RECEIVER FLASHING OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-510T



1. THE 3" ZEE-RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



ZEE CLOSURE



RECIEVER FLASHING



COUNTER FLASHING



COUNTER FLASHING



MIN. 16 GA. SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

HEAD WALL DETAIL; 3" ZEE-RIB RECEIVER FLASHING OPEN FRAMING

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE
Z-510TW



1. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RECIEVER FLASHING



COUNTER FLASHING



ZEE CLOSURE



COUNTER FLASHING



MIN. 16 GA. SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

HEAD WALL DETAIL RECEIVER FLASHING OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-51P0



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

HEAD WALL DETAIL RECEIVER FLASHING SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-51PS



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



REGLET FLASHING



COUNTER FLASHING



SUB-FLASHING



ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

HEAD WALL DETAIL
REGLET
SOLID SUBSTRATE

DATE: 5/23

PAGE\FILE
Z-51R

ZEE-LOCK PANEL



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



COUNTER FLASHING



SURFACE FLASHING



SUB-FLASHING



ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

HEAD WALL DETAIL SURFACE MOUNT SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-51SM



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

HEAD WALL DETAIL RECEIVER FLASHING SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-51TW



1. THE 3" ZEE-RIB TO BE USED ON APPLICATIONS WITH BATT INSULATION DRAPED OVER PURLINS WITH A THICKNESS OF GREATER THAN 3".
2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RECIEVER FLASHING



COUNTER FLASHING



MIN. 16 GA. SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RAKE WALL DETAIL; 3" ZEE-RIB RECEIVER FLASHING OPEN FRAMING

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE
Z-530T



1. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RECIEVER FLASHING



COUNTER FLASHING



MIN. 16 GA. SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RAKE WALL DETAIL RECEIVER FLASHING OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-53P0



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RECIEVER FLASHING



COUNTER FLASHING



SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RAKE WALL DETAIL RECEIVER FLASHING SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-53PS



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



REGLET FLASHING



SUB–FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RAKE WALL DETAIL REGLET SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–53R



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



COUNTER FLASHING



SURFACE FLASHING



SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RAKE WALL DETAIL SURFACE MOUNT SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-53SM



1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



RECIEVER FLASHING



COUNTER FLASHING



SUB-FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

RAKE WALL DETAIL RECEIVER FLASHING SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-53TW



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI–6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

4. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING



SPECIAL ZEE CLOSURE

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

ROOF TO FASCIA TRANSITION SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–60



NOTE: PLACE A DAB OF CAULK AT CLEAT FASTENER LOCATION, DRIVE FASTENER THROUGH CAULK, AND CAULK FASTENER HEADS.

DO NOT: RUN A CONTINUOUS BEAD OF CAULK ON CLEAT OR UNDER CLEAT

1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



TRANSITION FLASHING



CONTINUOUS CLEAT



SUB–FLASHING

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

SLOPE TRANSITION DETAIL SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–61



1. FIELD CUT SEAM AND BREAK PANEL TO DESIRED ANGLE OF ROOF TO FASCIA.

2. PLACE PANELS ON ROOF, USE THE CONTINUOUS ZEE–RIB OR ZEE–LOCK CLIP.

3. ONLY ONE SLOPE TRANSITION PER PANEL IS RECOMMENDED. MAXIMUM FASCIA SPAN FOR OPEN FRAMING IS 3'–0".

4. USE HAND SEAM CRIMPER ON ROOF PANELS AS REQUIRED TO KEEP PANELS IN PLACE.

5. CAULK JOINT BETWEEN PANEL LEGS; SEE DETAIL Z–63.

6. INSTALL ADDITIONAL MALE AND FEMALE LEGS AS SHOWN ON DETAIL Z–63. (THE ADDITIONAL LEGS CAN BE FIELD FABRICATED OR PURCHASED FROM THE FACTORY).

7. USE HAND SEAM CRIMPER TO SEAM PANEL ON FASCIA THEN MACHINE SEAM ROOF PANELS.

8. CAULK BETWEEN ROOF PANEL LEGS AND ADDITIONAL LEGS. SEE DETAIL Z–63.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

ROOF TO FASCIA TRANSITION SOLID SUBSTRATE

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–62







ADDITIONAL FEMALE LEG



SEAM SECTION AT FASCIA



ADDITIONAL MALE LEG

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

ROOF TO FASCIA TRANSITION SOLID SUBSTRATE

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE

Z-63



SEE DETAIL Z–71 FOR VALLEY FLASHING LAPPING

1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING. (REFERENCE INSTALLATION INSTRUCTIONS & LOAD CHARTS FOR MIN. FASTENER REQUIREMENTS)

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



VALLEY FLASHING

FORM VALLEY FLASHING FROM A FULL 42" OR 48" WIDE FLAT SHEET.
SEE TAPERED VALLEY DETAIL Z–73A



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

VALLEY DETAIL SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 1/23

PAGE\FILE
Z–70



SEE DETAIL Z–71D FOR VALLEY FLASHING LAPPING

1. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

2. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



VALLEY FLASHING

FORM VALLEY FLASHING FROM A FULL 42" OR 48" WIDE FLAT SHEET.
SEE TAPERED VALLEY DETAIL Z–73B



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

VALLEY DETAIL W/ DIVERTER SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–70D





BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

VALLEY DETAIL; ISOMETRIC OPEN FRAMING & SOLID SUBSTRATE

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–71





BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

VALLEY DETAIL; ISOMETRIC W/ 2" DIVERTER

OPEN FRAMING AND SOLID SUBSTRATE

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–71D



*FLASHING PROFILES AND NOTES, SEE DETAILS Z–70, Z–71, & Z–73A



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

VALLEY DETAIL OPEN FRAMING; 2" ZEE–RIB

ZEE–LOCK PANEL

DATE: 1/23

PAGE\FILE

Z–72



*FLASHING PROFILES AND NOTES, SEE DETAILS Z–70, Z–71, & Z–73A



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

VALLEY DETAIL OPEN FRAMING; 3" ZEE–RIB

ZEE–LOCK PANEL

DATE: 1/23

PAGE\FILE

Z–72T

FOR USE WITH 48" FLAT SHEET



NOTE: WHEN VALLEY FLASHING DIMENSIONS ARE LAID OUT ON FLAT SHEET YOU MUST START FROM CENTER OF FLAT SHEET AND MARK OUT THE DIMENSIONS TO BOTH OUTER SIDES OF THE FLAT SHEET

FOR USE WITH 42" FLAT SHEET



NOTE: WHEN VALLEY FLASHING DIMENSIONS ARE LAID OUT ON FLAT SHEET YOU MUST START FROM CENTER OF FLAT SHEET AND MARK OUT THE DIMENSIONS TO BOTH OUTER SIDES OF THE FLAT SHEET

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

TAPERED VALLEY DETAIL W/OUT DIVERTER

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE

Z-73A

FOR USE WITH 48" FLAT SHEET



NOTE: WHEN VALLEY FLASHING DIMENSIONS ARE LAID OUT ON FLAT SHEET YOU MUST START FROM CENTER OF FLAT SHEET AND MARK OUT THE DIMENSIONS TO BOTH OUTER SIDES OF THE FLAT SHEET

FOR USE WITH 42" FLAT SHEET



NOTE: WHEN VALLEY FLASHING DIMENSIONS ARE LAID OUT ON FLAT SHEET YOU MUST START FROM CENTER OF FLAT SHEET AND MARK OUT THE DIMENSIONS TO BOTH OUTER SIDES OF THE FLAT SHEET

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

TAPERED VALLEY DETAIL W/ 2" DIVERTER

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE

Z-73B



1. PIPE PENETRATION TO BE IN PAN OF PANEL ONLY
2. FIELD CUT HOLE IN PANEL 1" LESS THAN DIA. OF STACK. BACK CUT HOLE AND BEND PANEL UP AROUND STACK. CAULK CONTINUOUS.
3. IF PANELS ARE 30' OR LONGER, CUT HOLE TO ALLOW FOR THERMAL MOVEMENT.
4. IF PIPE IS METAL, IT MUST BE PAINTED TO PREVENT RUST RUN–OFF FROM STAINING PANELS.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PIPE PENETRATION
(PREFERRED METHOD)
IN PAN OF PANEL ONLY
OPEN FRAMING AND SOLID SUBSTRATE

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–80



DO NOT: RUN CAULK ON OR UNDER CONTINUOUS CLEAT

FOR ROOF PENETRATIONS LARGER THAN 4" SQUARE OR ROUND



BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

SQUARE PENETRATION PLAN VIEW

OPEN FRAMING AND SOLID SUBSTRATE

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–81



FOR ROOF PENETRATIONS LARGER THAN 4" SQUARE OR ROUND

1. SOLID SHEATHING IS REQUIRED AT THIS CONDITION WHEN USED OVER OPEN FRAMING (SEE DETAILS Z–85 & Z–86)

2. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



COUNTER FLASHING



SUB–FLASHING



ZEE CLOSURE



CONTINUOUS CLEAT

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

SQUARE PENETRATION SECTION A
OPEN FRAMING AND SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–82

FOR ROOF PENETRATIONS LARGER THAN 4" SQUARE OR ROUND



1. SOLID SHEATHING IS REQUIRED AT THIS CONDITION WHEN USED OVER OPEN FRAMING (SEE DETAILS Z–85 & Z–86)

2. SOLID SHEATHING (NOT BY BERRIDGE) TO MEET ENGINEERING AND ARCHITECTURAL SPECIFICATIONS MINIMUM REQUIREMENTS, REFERENCE INSTALLATION INSTRUCTIONS.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



WRAP FLASHING



SUB–FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

SQUARE PENETRATION SECTION B
OPEN FRAMING AND SOLID SUBSTRATE

ZEE–LOCK PANEL

DATE: 5/23

PAGE\FILE
Z–83

FOR ROOF PENETRATIONS LARGER THAN 4" SQUARE OR ROUND





BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

SQUARE PENETRATION ISOMETRIC

OPEN FRAMING AND SOLID SUBSTRATE

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE

Z-84

OPEN FRAMING INSTALLATION, FOR ROOF PENETRATIONS LARGER THAN 4" SQUARE OR ROUND



EAVE (Z–86)

A 40–MIL MINIMUM THICKNESS, SELF–ADHERING MEMBRANE IS REQUIRED. REFER TO WWW.BERRIDGE.COM FOR LIST OF APPROVED PRODUCTS.

16 GA. HAT SECTION SIZED TO FIT OVER PURLIN AND TO ACCOMMODATE THE DEPTH OF THE BERRIDGE CORRUGATED S–DECK.





SECTION–A

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PENETRATION LARGER THAN 4"; 2" ZEE–RIB OPEN FRAMING

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–85



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART (ZI-6)

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: FOR USE WITH 2" ZEE-RIB

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING



16 GA. SUPPORT ANGLE

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

EAVE DETAIL; SOLID SHEATHING FOR ROOF ACCESS OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-86



*NOTE: CONTINUOUS 2" AND 3" ZEE-RIBS ARE REQUIRED TO HAVE VINYL WEATHERSEAL

USE SHIMS TO KEEP THE ZEE-RIB FROM FALLING INTO THE VALLEYS OF THE CORRUGATED DECK.

A 40-MIL MINIMUM THICKNESS, SELF-ADHERING MEMBRANE IS REQUIRED. REFER TO WWW.BERRIDGE.COM FOR LIST OF APPROVED PRODUCTS.



SECTION-A

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

PENETRATION LARGER THAN 4"; 3" ZEE-RIB W/ THERMAL BLOCKS & INSULATION

DATE: 5/23

ZEE-LOCK PANEL

PAGE\FILE

Z-87



1. THE "GAP" BETWEEN EAVE FLASHING AND PANEL (SEE DETAIL ABOVE) CAN BE INCREASED TO ALLOW FOR LINEAR EXPANSION AND CONTRACTION OF PANELS. NOTE 1/2" OF PAN MUST BE ENGAGED WITH EAVE FLASHING WHEN PANEL HAS EXPANDED TO ITS MAXIMUM LENGTH REFER TO NOMINAL LINEAR EXPANSION CHART

2. GAP BETWEEN EAVE FLASHING AND PANEL MUST BE ADJUSTED TO SUIT TEMPERATURE DURING INSTALLATION.

3. REFERENCE BERRIDGE'S WEB SITE FOR APPROVED UNDERLAYMENT AND CAULK TYPES CONSULT BERRIDGE MANUFACTURING'S ENGINEERING DEPARTMENT REGARDING FASTENER TYPE & SPACING.

NOTE: FOR USE WITH 3" ZEE-RIB

NOTE: ALL FLASHING GAUGES TO BE EQUAL TO THE ASSOCIATED PANEL GAUGE UNLESS NOTED OTHERWISE

F = FINISH SIDE
FV = FIELD VERIFY



EAVE FLASHING

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

EAVE DETAIL; SOLID SHEATHING FOR ROOF ACCESS OPEN FRAMING

ZEE-LOCK PANEL

DATE: 5/23

PAGE\FILE
Z-88

USE ONLY STAINLESS STEEL OR ALUMINUM LIGHTNING RODS



LIGHTNING CONTROL SYSTEMS ON A PROJECT ARE TO THE DISCRETION OF THE ARCHITECT OR PROJECT DESIGNER. BERRIDGE MANUFACTURING CO. MAKES NO RECOMMENDATIONS AS TO WHEN TO USE A LIGHTNING CONTROL SYSTEM.

IF A LIGHTNING CONTROL SYSTEM IS SPECIFIED, ALL COMPONENTS OF THE SYSTEM SHOULD BE OF MATERIAL COMPATIBLE WITH THE BERRIDGE ROOFING SYSTEM; ALUMINUM AND/OR STAINLESS STEEL ARE TWO METALS THAT WORK WELL. WHEN AN INCOMPATIBLE MATERIAL SUCH AS COPPER IS USED ELECTROLYTIC CORROSION OCCURS DUE TO DISSIMILAR METALS CONTACTING IN THE PRESENCE OF AN ELECTROLYTE, SUCH AS WATER. THE DISSIMILAR METALS SET UP A GALVANIC ACTION THAT RESULT IN THE DETERIORATION OF ONE OF THEM. BERRIDGE MANUFACTURING CO. WILL NOT BE HELD LIABLE FOR ANY CLAIMS DUE TO FAILURES CAUSED BY DISSIMILAR METALS.

LIGHTNING CONTROL SYSTEMS NORMALLY REQUIRE ANCHORAGE FOR THE AIR TERMINALS AND THE CABLE BASES. IF ANCHORAGE TO BERRIDGE MATERIAL IS MADE WITH AN ADHESIVE, COMPATIBILITY TO KYNAR/HYLAR PAINT SHOULD BE INVESTIGATED. IF CUTTING HOLES IN THE BERRIDGE ROOFING SYSTEM IS REQUIRED FOR ANCHORAGE, RUBBERIZED BOOTS (REFER TO THE LIGHTNING CONTROL MANUFACTURER FOR SUITABLE BOOTS) SHOULD BE USED AND SEALED TO THE BERRIDGE ROOF SYSTEM WITH TREMCO SPECTREM ONE CAULKING. IT IS POSSIBLE THAT CABLES MAY VIBRATE IN WIND AND CAUSE DAMAGE TO THE METAL AND PAINT FINISH, THEREFORE CABLES SHOULD NOT BE ALLOWED TO LAY ON TOP OF THE ROOFING PANELS OR FLASHING.

BERRIDGE MANUFACTURING WILL NOT BE RESPONSIBLE FOR WATERTIGHTNESS OF THE LIGHTNING CONTROL SYSTEM AND SHOULD BE COVERED BY THE LIGHTNING CONTROL SYSTEM INSTALLER OR MANUFACTURER.

LIGHTNING CONTROL SYSTEMS ARE TO BE DESIGNED BY AND INSTALLED BY QUALIFIED PROFESSIONALS. BERRIDGE MANUFACTURING CO. SHALL HAVE NO LIABILITY TO THE RECOMMENDATIONS OUTLINED IN THIS LETTER.



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL. 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–RIB (CONTINUOUS) * – ONE PIECE ASSEMBLY FABRICATED FROM 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–RIB LOCATED AT EACH PANEL SIDE LAP BEING CONTINUOUS AND EQUAL TO LENGTH OF "METAL ROOF DECK PANELS" (ITEM 1) (2" ZEE–RIB)

3. FASTENERS (SCREWS) – FOR ATTACHING "ZEE–CLIP RIB" (ITEM 2) TO PURLINS. USE #12 x 1 IN. SELF–DRILLING, SELF–TAPPING STEEL SCREWS. TWO FASTENERS AT EACH PURLIN LOCATION.

4. PURLINS – NO. 16 MSG (MIN. YIELD STRENGTH 50,000 PSI) COATED STEEL 5'–0" MAXIMUM SPACING.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL 90 APPROVED ASSEMBLY
SEAM SECTIONS AND FASTENER
SPECS CONSTRUCTION NO. 312

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–90



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL, 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–RIB (CONTINUOUS) * – ONE PIECE ASSEMBLY FABRICATED FROM 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–RIB LOCATED AT EACH PANEL SIDE LAP BEING CONTINUOUS AND EQUAL TO LENGTH OF "METAL ROOF DECK PANELS" (ITEM 1) (2" ZEE–RIB)

3. PURLINS – NO. 16 MSG (MIN. YIELD STRENGTH 50,000 PSI) COATED STEEL 5'–0" MAXIMUM SPACING.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL 90 APPROVED ASSEMBLY
PURLIN SPACING
CONSTRUCTION NO. 312

DATE: 9/20

ZEE–LOCK PANEL

PAGE\FILE
Z–91



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL, (MIN. YIELD STRENGTH 40,000 PSI) 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–RIB (CONTINUOUS) * – ONE PIECE ASSEMBLY FABRICATED FROM 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–RIB LOCATED AT EACH PANEL SIDE LAP BEING CONTINUOUS AND EQUAL TO LENGTH OF "METAL ROOF DECK PANELS" (ITEM 1) (3" ZEE–RIB)

3. FASTENERS (SCREWS) – FOR ATTACHING "ZEE–RIB" (ITEM 2) TO PURLINS (ITEM 5). USE #12 x 1 IN. SELF–DRILLING, SELF–TAPPING STEEL SCREWS. TWO FASTENERS AT EACH PURLIN LOCATION.

4. THERMAL BLOCK – 3" BY 16" BY 1" EXTRUDED POLYSTYRENE. (OPTIONAL)

5. PURLINS – NO. 16 MSG (MIN. YIELD STRENGTH 50,000 PSI) COATED STEEL 5'–0" MAXIMUM SPACING.

6. INSULATION – (NOT SHOWN) (OPTIONAL) 6" VINYL FACED COMPRESSIBLE INSULATION. REFER TO DETAIL Z–93.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL 90 APPROVED ASSEMBLY ZEE–LOCK PANEL WITH CONTINUOUS ZEE–RIB AND BLANKET INSULATION AND 1" THERMAL BLOCK AND 16 GA. PURLINS AT 5'–0" O.C. MAX. UL CONSTRUCTION NO. 312

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–92



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL, (MIN. YIELD STRENGTH 40,000 PSI) 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–RIB (CONTINUOUS) * – ONE PIECE ASSEMBLY FABRICATED FROM NO. 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–RIB LOCATED AT EACH PANEL SIDE LAP BEING CONTINUOUS AND EQUAL TO LENGTH OF "METAL ROOF DECK PANELS" (ITEM 1) (3" ZEE–RIB)

3. THERMAL BLOCK – 3" BY 16" BY 1" EXTRUDED POLYSTYRENE. (OPTIONAL)

4. INSULATION – 6 IN. VINYL FACED COMPRESSIBLE INSULATION. (OPTIONAL)

5. PURLINS – NO. 16 MSG (MIN. YIELD STRENGTH 50,000 PSI) COATED STEEL 5'–0" MAXIMUM SPACING.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL 90 APPROVED ASSEMBLY ZEE–LOCK PANEL WITH CONTINUOUS ZEE–RIB AND BLANKET INSULATION AND 1" THERMAL BLOCK AND 16 GA. PURLINS AT 5'–0" O.C. MAX. UL CONSTRUCTION NO. 312

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–93



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL, (MIN. YIELD STRENGTH 40,000 PSI) 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–RIB (CONTINUOUS) * – ONE PIECE ASSEMBLY FABRICATED FROM NO. 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–RIB LOCATED AT EACH PANEL SIDE LAP BEING CONTINUOUS AND EQUAL TO LENGTH OF "METAL ROOF DECK PANELS" (ITEM 1) (2" ZEE–RIB)

3. FASTENERS (SCREWS) –
   A. FOR ATTACHING "ZEE–RIB" (ITEM 2) TO LINER (ITEM 6). USE #12 SELF–DRILLING STEEL SCREW THROUGH RIGID BOARD AND CONNECTED TO METAL DECK AT 18" ON CENTER. FASTENER LENGTH TO BE ADJUSTED TO ACCOUNT FOR THICKNESS OF RIGID INSULATION AND LINER PANEL WITH 3/4" MINIMUM PENETRATION INTO METAL DECK.
   B. FOR ATTACHING "ZEE–RIB" (ITEM 2) TO PURLIN (ITEM 7) USE #12 SELF–DRILLING STEEL SCREW AT EACH PURLIN LOCATION. FASTENER LENGTH TO BE ADJUSTED TO ACCOUNT FOR THICKNESS OF RIGID INSULATION AND LINER PANEL WITH 3/4" MINIMUM PENETRATION INTO THE PURLIN.
   C. FOR CONNECTION OF LINER (ITEM 6) TO PURLIN (ITEM 7) USE #10 X $\frac{3}{4}$" FASTENER SPACED $5\frac{1}{2}$" ON CENTER. FASTENERS AT SIDE LAP TO BE SPACED 8" ON CENTER.

4. BERRIDGE APPROVED PEEL & STICK OR #30 FELT UNDERLAYMENT.

5. INSULATION – MAXIMUM 4" THICK, 2.25 PCF DENSITY 20 PSF COMPRESSIVE STRENGTH RIGID CLOSED CELL POLYISOCYANURATE CORE FIBERGLASS FACED INSULATION.

6. SUBSTRUCTURE (LINER) – NO. 24 MSG (MIN. YIELD STRENGTH 40,000 PSI) COATED STEEL. CORRUGATION HEIGHT TO BE MINIMUM 3/4". ENDLAPS TO OCCUR OVER PURLINS WITH PANELS OVERLAPPED MINIMUM 4".

7. PURLINS – NO. 16 MSG (MIN. YIELD STRENGTH 50,000 PSI) COATED STEEL. SPACING TO BE:
   A. 5'–0" ON CENTER WHEN ITEM #2 IS CONNECTED TO ITEM #7
   B. 4'–0" ON CENTER WHEN ITEM #2 IS CONNECTED TO ITEM #6

BERRIDGE MANUFACTURING COMPANY
Roofs of Distinction

UL 90 APPROVED ASSEMBLY ZEE–LOCK PANEL WITH CONTINUOUS ZEE–RIB AND 4" RIGID INSULATION BOARD OVER BERRIDGE 24 GA. CORRUGATED S–DECK AND 16 GA. PURLINS AT 5'–0" O.C. MAX. UL CONSTRUCTION NO. 335

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–94



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL, (MIN. YIELD STRENGTH 40,000 PSI) 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–RIB (CONTINUOUS) * – ONE PIECE ASSEMBLY FABRICATED FROM NO. 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–RIB LOCATED AT EACH PANEL SIDE LAP BEING CONTINUOUS AND EQUAL TO LENGTH OF "METAL ROOF DECK PANELS". (ITEM 1) (2" ZEE–RIB)

3. BERRIDGE APPROVED PEEL & STICK OR #30 FELT UNDERLAYMENT.

4. INSULATION – MAXIMUM 4" THICK, 2.25 PCF DENSITY 20 PSF COMPRESSIVE STRENGTH RIGID CLOSED CELL POLYISOCYANURATE CORE FIBERGLASS FACED INSULATION.

5. SUBSTRUCTURE (LINER) – NO. 24 MSG (MIN. YIELD STRENGTH 40,000 PSI) COATED STEEL. CORRUGATION HEIGHT TO BE MINIMUM 3/4". ENDLAPS TO OCCUR OVER PURLINS WITH PANELS OVERLAPPED MINIMUM 4".

6. PURLINS – NO. 16 MSG (MIN. YIELD STRENGTH 50,000 PSI) COATED STEEL. SPACING TO BE:
   A. 5'–0" ON CENTER WHEN ITEM #2 IS CONNECTED TO ITEM #7
   B. 4'–0" ON CENTER WHEN ITEM #2 IS CONNECTED TO ITEM #6

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL 90 APPROVED ASSEMBLY ZEE–LOCK PANEL WITH CONTINUOUS ZEE–RIB AND 4" RIGID INSULATION BOARD OVER BERRIDGE 24 GA. CORRUGATED S–DECK AND 16 GA. PURLINS AT 5'–0" O.C. MAX. UL CONSTRUCTION NO. 335

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–95



1. BERRIDGE ZEE–LOCK PANEL * – NO. 24 MSG MINIMUM THICKNESS COATED STEEL, (MIN. YIELD STRENGTH 40,000 PSI) 16 IN. WIDE, 2 IN. HIGH. PANELS CONTINUOUS OVER TWO OR MORE SPANS WITHOUT END LAPS. ADJACENT PANELS ARE SEAMED TOGETHER ALONG SIDE LAPS USING AN ELECTRIC SEAMING TOOL.

   BERRIDGE MANUFACTURING CO. – "ZEE–LOCK PANEL"

2. BERRIDGE ZEE–CLIP – ONE PIECE, 2" HIGH AND 3" LONG, ASSEMBLY FABRICATED FROM NO. 24 MSG COATED STEEL. (MIN. YIELD STRENGTH 40,000 PSI) ZEE–CLIP LOCATED 36" ON CENTER AT EACH PANEL SIDE JOINTS.

3. FASTENERS (SCREWS) –
   A. FOR ATTACHING "ZEE–CLIPS" (ITEM 2) TO PLYWOOD (ITEM 5) USE #10 X 1" LONG PAN HEAD STEEL SCREWS. 2 PER CLIP.
   B. FOR ATTACHING "ZEE–CLIPS" (ITEM 2) TO JOISTS (ITEM 6) #8 X $1\frac{1}{2}$" LONG PAN HEAD WOOD SCREW SPACED 12" ON CENTER AT PLYWOOD TO JOIST CONNECTION AND AT PLYWOOD ENDS.

4. BERRIDGE APPROVED PEEL & STICK OR #30 FELT UNDERLAYMENT.

5. SUBSTRUCTURE (PLYWOOD): NOMINAL 5/8" THICK, EXPOSURE SHEATHING SPAN C–D 40/20 PLYWOOD.

6. JOISTS: NOMINAL 2"X4" AT MAXIMUM 2'–0" ON CENTER.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL 90 APPROVED ASSEMBLY ZEE–LOCK PANEL
WITH INDIVIDUAL ZEE–CLIPS OVER 5/8" PLYWOOD
UL CONSTRUCTION NO. 403

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE
Z–96



1. IN ORDER TO QUALIFY FOR A FIRE–RESISTANT RATING, THE ROOF SYSTEM CANNOT MAKE A PENETRATION IN THE INSULATION SYSTEM. THE ZEE LOCK–PANEL, IN ORDER TO MAKE POSITIVE ATTACHMENT, MUST BE ATTACHED TO A CORRUGATED SUBSTRATUM (IF THE INSULATION SYSTEM HAS NO NAILABLE SURFACE). THE CORRUGATED SUBSTRATUM IS TO BE MOUNTED DIRECTLY TO THE INSULATION SYSTEM WITH FASTENERS FASTENED THROUGH INTO THE STRUCTURAL STEEL DECK.

2. THIS ASSEMBLY QUALIFIES FOR THE FOLLOWING UL FIRE–RESISTANT ROOF ASSEMBLIES: UL DESIGN NUMBER P225, P230, P237, P250, P259, P508, P510, P514, AND P227 USING CELLULAR GLASS BLOCK IN LIEU OF MINERAL INSULATION BOARD.

3. ADDITIONAL INFORMATION REGARDING THIS ASSEMBLY IS AVAILABLE IN THE UL FIRE RESISTANCE DIRECTORY.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL FIRE RESISTANCE ROOF ASSEMBLY

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–100



1. IN ORDER TO QUALIFY FOR A FIRE–RESISTANT RATING, THE ROOF SYSTEM CANNOT MAKE A PENETRATION IN THE INSULATION SYSTEM. THE ZEE LOCK–PANEL, IN ORDER TO MAKE POSITIVE ATTACHMENT, MUST BE ATTACHED TO A CORRUGATED SUBSTRATUM (IF THE INSULATION SYSTEM HAS NO NAILABLE SURFACE). THE CORRUGATED SUBSTRATUM IS TO BE MOUNTED DIRECTLY TO THE INSULATION SYSTEM WITH FASTENERS FASTENED THROUGH INTO THE STRUCTURAL STEEL DECK.

2. THIS ASSEMBLY QUALIFIES FOR THE UL FIRE–RESISTANT ROOF ASSEMBLIES: P512 & P518, LESS THE MINERAL BOARD REQUIREMENTS.

3. ADDITIONAL INFORMATION REGARDING THIS ASSEMBLY IS AVAILABLE IN THE UL FIRE RESISTANCE DIRECTORY.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL FIRE RESISTANCE ROOF ASSEMBLY

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–101



1. IN ORDER TO QUALIFY FOR A FIRE–RESISTANT RATING, THE ROOF SYSTEM CANNOT MAKE A PENETRATION IN THE INSULATION SYSTEM. THE ZEE LOCK–PANEL, IN ORDER TO MAKE POSITIVE ATTACHMENT, MUST BE ATTACHED TO A CORRUGATED SUBSTRATUM (IF THE INSULATION SYSTEM HAS NO NAILABLE SURFACE). THE CORRUGATED SUBSTRATUM IS TO BE MOUNTED DIRECTLY TO THE INSULATION SYSTEM WITH FASTENERS FASTENED THROUGH INTO THE STRUCTURAL STEEL DECK.

2. THIS ASSEMBLY QUALIFIES FOR THE FOLLOWING UL FIRE RESISTANT ROOF ASSEMBLIES: UL DESIGN NUMBER P701, P711, P713, P717, P719, P720, P722, P723, P726, P731, P732, P734, P801, P815, P819 AND P824 ONLY USING SPRAYED ON FIBER IN LIEU OF CEMENTITIOUS MIXTURE.

3. ADDITIONAL INFORMATION REGARDING THIS ASSEMBLY IS AVAILABLE IN THE UL FIRE RESISTANCE DIRECTORY.

BERRIDGE MANUFACTURING COMPANY

Roofs of Distinction

UL FIRE RESISTANCE ROOF ASSEMBLY

DATE: 5/23

ZEE–LOCK PANEL

PAGE\FILE

Z–102